

FILED

JUL 14 9 46 AM '95

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located in:

Corner Code ##

- 1. Public Land Survey T 4N R 5E K-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.#418m

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked in cell G5.

I, Edward Anderson, in a field survey on June 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes dated: May 11, 1823
G.L.O. Witnesses: W. Oak 16" N23"E 56 Lks
W. Oak 26" S31"W 37 Lks

Additional history data on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Pipe. Fit witnesses by Benton, Boss, C.H.M.P., and Anderson

001 01995

COMPLETION


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 N.W. COR. SEC 13, T4N-R5E

Set 1 1/4" x 36" Breakaway iron pipe with brass cap (Liv. Co. Mon. Cor.) in centerline intersections of Hogan and Green Roads
N28°E, 86.25' Spike W/S 10" Twin Elm
S21°E 55.08' Spike N.E/S 18" Hickory
S78°W 78.37' Spike N/S 24" Oak
N55°W 58.06' Spike S/S 24" Hickory

Signed by

[Signature]



Date July 5, 1995

Surveyor's Michigan License No. 11495

NEED TO BE RE-EXAMINED BY THE BOARD OF SURVEYORS



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.
Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

SUMMARY

April 4, 1995

K-5 N.W. CORNER OF SECTION 13, T4N-R5E, DEERFIELD TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

Found 1" pipe at the centerline intersection of Hogan and Green Roads (gravel)

Checked and measured to witnesses we found. Found all of Benton witness and they checked, Pages 10, 13 and 14, this dossier. Found all Boss witnesses and they checked page 21 this dossier. Found 2 of 4 of C.H.M.P. witnesses and they checked, page 16 this dossier. Found all of Anderson witnesses and they checked, pages 17 and 19 this dossier.

Distance from the N.W. corner to the North 1/4 corner of said Section 13 is 2682.08' Boss survey, page 20 this dossier.

Distance from the NW corner to the West 1/4 corner of said Section 13 is 2662.01' as measured in field by E. E. Anderson on April 3, 1995, page 6 this dossier.

Made a clean sweep of immediate area and found no additional corners or irons.

Gravel roads running north, south, east and west. Roads are flat in all directions.

Terrain is wooded to South and N.W.; open to N.E.

Area is fairly good for G.P.S.

Came to the conclusion that the 1" pipe we found is the correct N.W. corner of said Section 32.

Edward E. Anderson
P.S.#11495

T4N R5E K-5