

SURVEY & REMONUMENTATION

DEC 13 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners of **COMMISSION SURVEY**
LIVINGSTON
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> R <u>5</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 NOV 9 9 45 AM '93
 NANCY HAVILLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843
 L.S.C. #30^m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EDWARD ANDERSON, in a field survey on AUGUST 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO NOTES DATED May 1, 1823
 GLO WITNESSES W. Oak 36" N25°W, 22 LKS
 W. Oak 8" S31 1/2°E, 35 LKS


ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" 36" Iron. Fit witnesses by Garlock (Professional Surveyor), Benton (Professional Surveyor, Boss Engineering).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-12 WEST 1/4 CORNER SECTION ³⁶~~35~~, T4N-R5E
 Set 1 1/4" x 36" Breakaway Iron Pipe with Brass Cap (Livingston County Monument Corner) 5' West of Centerline Green Road
 N30°E, 55.90' Spike W/S 28" Oak
 S70°E, 30.55' Spike S/S 20" Walnut
 S30°E, 74.09' Spike N/S 22" Hickory
 N70°W, 14.64' Spike S/S 8" Poplar

Approved by Livingston County
 Monument Peer Group
 October 10, 1993

Signed by *E. Anderson*
 Surveyor's Michigan License No. 11495



Date November 2, 1993



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

September 1, 1993

SUMMARY

K-12 WEST 1/4 CORNER SECTION 36, T4N-R5E, DEERFIELD TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" iron 5'± west of centerline of Green Road (gravel);
checked and measured to witnesses we found. The witnesses were the
same by Farlock, Benton and Boss, Pages 6C, 7, 9B, 11, and 13, this
dossier.

The same corner was used by Boss, Benton & Garlock from 1976 thru
1993, Pages 6C, 7, 9B, 11, and 13, this dossier.

Distances from West 1/4 corner to the NW corner of said Section 36
are shown on Benton Survey as 2652.95', Page 7, this dossier.

Distances from W 1/4 to the SW corner of said Section 36 as 2652.70
on Boss survey, and 2652.55 on Benton Survey, Pages 6A, 8, and 9A,
this dossier.

Made a clean sweep of immediate area and found no additional corners
or irons.

Found old wire fence to the East and no occupation to the West.
Green Road (gravel) runs uphill to North and downhill to South.

Terrain is hilly and wooded. Swamp to the SE.

Came to the conclusion that 1/2" iron we found was the correct
West 1/4 corner of said Section 36.

E. Anderson
Edward E. Anderson
P.S.#11495

