

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

SEP 15 12 02 PM '95

Filing Requirement of Act 74, Mich. P.A. 1970

HANGY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

For corners in Livingston Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>4N</u>	R	<u>5E</u>	<u>M-6</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

L.S.C.# 429m  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Edward Anderson, in a field survey on August 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NOTES DATED May 11, 1823  
GLO WITNESSES B. Ash 8" S69°W 40 Lks  
Elm 10" N20°W 39 Lks

ADDITIONAL HISTORICAL DATA ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET IRON AT 1/2 DISTANCE BETWEEN NE CORNER AND SE CORNER AND ON LINE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 E 1/4 COR SEC 13 T4N-R5E  
Set 1 1/4" x 36" iron pipe with Brass Cap (Liv. Co. Mon. Cor.)  
in swamp  
N49°E 31.30' 1" x 36" witness pipe  
S42°E 29.45' 1" x 36" witness pipe  
S49°W 26.95' 1" x 36" witness pipe  
N24°W 27.85' 1" x 36" witness pipe

Signed by E. Anderson  
Surveyor's Michigan License No. \_\_\_\_\_  
ANDERSON  
11495  
ENGINEER  
NO. 11495  
of Surveyor & Prof. Engineer

Date August 21, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-19-95, CO. REP. JFD



EDWARD E. ANDERSON, P.S., P.E.  
RICHARD F. FRANK, P.S.  
BRIAN R. SHALTZ, C.S.T.

Members of:  
Michigan Society of Professional Surveyors  
American Congress on Surveying and Mapping  
American Society of Civil Engineers

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

SUMMARY


July 10, 1995

M-6 EAST 1/4 CORNER SECTION 13, T4N-R5E, DEERFIELD TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN

Found no existing physical evidence of a corner, or any record of witnesses to the corner. The corner would fall in a swampy area. There are no trees, fences, or other physical evidence to indicate the location of this corner. Therefore, I would consider this corner as a lost corner, rather than an obliterated corner.

I have come to the conclusion that I will set the East 1/4 corner of said Section 13 one half way and on line between the N.E. and the S.E. corners of said Section 13, as accepted and approved by the Livingston County Remonumentation Peer Group. See Sheets 12 and 13, this dossier.

*E. Anderson*  
Edward E. Anderson  
PS#11495




August 21, 1995

At the time I appeared before the Peer Group on July 19, 1995, I was asked if there was any evidence of fence lines. I said that there was not. However, in my research of this corner, I did find an old east and west fence line running from the east side of Major Road (Major Road is on the approximate East 1/8 line of said Section 13) Easterly 800' to the easterly terminus.

This fence connected to an old fence running north and south. Also, there was no evidence of a fence line running to the west of said Major Road. I located this east and west fence and found that it was not straight. (See Sheet 14 this dossier. I therefore determined that neither it or the old north and south fence lines were sufficient evidence as to establishing the location of the direction and location of the East 1/4 corner of said Section 13. I therefore hold to my original conclusion as stated above.

*E. Anderson*  
Edward E. Anderson  
PS#11495



T4N-R5E  
M-6  
P-4