

SURVEY & REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILED

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston Located In: Corner Code #
(County)

1. Public Land Survey T 4N R 5E G 9
T _____ R _____ G _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

2000 OCT 30 A 9:20

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1323 m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on July 2000 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Section corner common to Sections 21, 22, 27, & 28, T4N-R5E, Deerfield Township, Livingston County, Michigan.
1823 Wood post placed by Sylvester Sibley, D.S.: S08E 43 lks 30" W. Oak
N14.5W 13 lks 12" Oak.
1875 Post set by Wm. Bullock, C.S.: S67 3/4W 97 lks 8" Hickory
1981 Act 132 by G. Boss, L.1013, P.888; "T" iron at road intersection. Lists three witnesses.
1999 Act 74 by M. Millettics, LSC #1857; fnd 1/2" rerod. Lists four witnesses.
1999 Unrecorded survey by J. K. Smith, same as Act 74 by Millettics.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Section corner common to Sections 21, 22, 27, & 28, T4N-R5E, Deerfield Township, Livingston County, Michigan.
Found no evidence of original government corner. Found 1/2" iron in centerline-centerline of Dean and Mack Road. Verified the position of the 1/2" iron with record witnesses and measurements from 1981 to present.

Measurements:

<u>To F-9</u>	<u>To H-9</u>	<u>To G-10</u>	<u>To G-8</u>
1823 39.82ch (2628.12')	1823 39.84ch (2629.44')	1823 40ch (2640')	1823 40ch (2640')
1875 39.89ch (2632.74')	1875 39.78ch (2625.48')	1999 2653.79' (40.21ch)	1981 2640.27' (40.00ch)
1981 2644.38' (40.07ch)	2000 2631.41' (39.87ch)	2000 2653.72' (40.21ch)	
2000 2644.33' (40.07ch)			

Found no conflicting evidence in the vicinity of this position. We recommend that the found iron be accepted as the best available evidence of the position of the original government corner and be replaced with a standard Livingston County breakaway monument and brass cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Section corner common to Sections 21, 22, 27, & 28, T4N-R5E, Deerfield Township, Livingston County, Michigan.
Set standard Livingston County breakaway monument and brass cap stamped "G-9 39096".
N45E 67.71' Found spike in NW face of 15" Oak (R=67.70')
N20W 94.24' Found spike in East face of 30" Oak (R=94.16')
N45W 37.94' Southeast corner of concrete post (R=37.94')
S45E 102.89' Found spike in NE face of utility pole (R=102.84')



Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____