

OCT 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

9-

SEP 15 12 03 PM '95

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
18843

For corners in Livingston Located In: Corner Code #  
(County)

- 1. Public Land Survey T 4N R 6E C-11
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

L.S.C.# 436m  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Edward E. Anderson in a field survey on July 11, 1995  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO NOTES DATED APRIL 5, 1823  
GLO WITNESSES W.OAK 22" N59°E 41 Lks  
B. OAK 10" S42°W 35 Lks

Additional historical data on back


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1/2" capped iron fit witness by Albright, Boss, Ward and Benton

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 N.W. COR. SEC 32 T4N-R6E  
Set 1 1/4" x 36" Breakaway iron pipe with Brass cap (Livingston County Mon. Cor.) at intersection of fences  
East, 19.93' spike N/S 24" Hickory  
S15°W 31.20' spike E/S 12" Oak  
N58°W 22.56' spike E/S 12" Ash  
N01°W 37.50' spike E/S 12" Ash

Signed by Edward E. Anderson  
Surveyor's Michigan License No. 11495



Date July 17, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

P.A. 345 1960. APPROVED BY LIVINGSTON COUNTY  
FEEL GROUP OK 6/7/95 ON REF VED



EDWARD E. ANDERSON, P.S., P.E.  
RICHARD F. FRANK, P.S.  
BRIAN R. SHALTZ, C.S.T.

Members of:  
Michigan Society of Professional Surveyors  
American Congress on Surveying and Mapping  
American Society of Civil Engineers

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

SUMMARY

May 3, 1995

C-11 NORTHWEST CORNER SECTION 32, T4N-R6E, TYRONE TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" capped rerod (#23518) on the northwest side of corner fence post at the intersection of old fence running east, west, and south.

Checked and measured to witnesses we found. Found 2 of 3 of Albright witnesses, and they checked, pages 10 and 15 this dossier.

Found 3 of 4 of Grant Ward, Boss, and Benton witnesses and they checked, pages 12, 14, 16, 17, 19, 20, and 22 this dossier.

Distance from the NW corner to the North 1/4 corner of said Section 32 is 2625.25' on Boss survey, page 21 this dossier.

Distance from the N.W. to the West 1/4 corner of said Section 32 is 2665.21' on Grant ward survey, and 2666.92' on Albright survey, pages 16 and 24 this dossier.

Made a clean sweep of immediate area and found no additional markers or irons.

Terrain is wooded in all directions.

Old fence line to east, west, and south.

Poor location for G.P.S.

Came to the conclusion that the 1/2" capped rerod we found is the correct N.W. corner of said Section 32.

*E. Anderson*  
Edward E. Anderson  
P.S.#11495

T4N-R6E-C-11 p54