

FILED

JUL 14 9 46 AM '95

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Livingston  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4 N R 6 E C-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

L. S. C. #420m

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward E. Anderson, in a field survey on June 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. Notes dated April 5, 1823
- G.L.O. Witnesses W. Oak 15" S16°E 18 Lks
- W. Oak 12" N13°W 116 Lks

Additional historical data on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Capped iron. Fit witnesses by Boss, D. Ross, Benton, Albright, and Hughes.


SURVEYOR  
MONUMENTATION  
OCT 11 1895  
CONFIRMED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 S.W. COR. SEC. 32 T4N-R6E
- Set 1 1/4" x 36" iron pipe with brass cap (Liv. Co. Mon. Cor.)
- 3' east of East edge of Blacktop (Linden Road)
- N58°E 40.25' Spike W/S 36" Maple
- S22°E 52.82' S.W. corner house
- S80°E 45.85' Spike E/S 18" Triple Oak
- N30°W 92.03' N.E. corner house

PA. 345 1980, APPROVED BY LIVINGSTON COUN  
PEER GROUP ON 5-3-95 CO. REP JED

Signed by E. Anderson  
Surveyor's Michigan License No. 11495



Date July 5, 1995



EDWARD E. ANDERSON, P.S., P.E.  
RICHARD F. FRANK, P.S.  
BRIAN R. SHALTZ, C.S.T.

Members of:  
Michigan Society of Professional Surveyors  
American Congress on Surveying and Mapping  
American Society of Civil Engineers

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

SUMMARY

APRIL 27, 1995

C-13 S. W. CORNER OF SECTION 32, T4N-R6E, TYRONE TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" capped iron pipe (P.S. number obliterated) 3' east of the east edge of black top pavement (Linden Road)

Checked and measured to witnesses we found. Found all of Boss, D. Ross, and P. Benton witnesses, and they checked, pages 21, 22, 23, 25, and 32 this dossier. Found 4 of 8 of Albright witnesses, and they checked, pages ~~32~~, 28, 33, and 34 this dossier. Found 3 of 4 of Hughes witnesses and they checked, page 31 this dossier.

Found N.E. corner Section 6, T3N-R6E. Didn't find any of Garlock of Albright witnesses, pages 27, and 29 this dossier. Found all of Desine and Boss witnesses and they checked, pages 36 and 37 this dossier.

Distance from the S.W. corner to the S 1/4 corner of said Section 32 is 2612.59' on Benton Survey, page 23 this dossier.

Distance from the S.W. corner to the W 1/4 corner of said Section 32 is 2659.07' on Hughes Survey, page 30 this dossier.

Made a clean sweep of immediate area and found a broken off metal fence post 2.65' south of the S.W. corner of Section 32.

Centerline of black top road (Linden Road) running to the north and said road to the south curves to the west. Roads flat both north and south.

Terrain is open in all directions. House to the N.W., N.E., and S.E. Store to the S.W.

Occupation consists of wood rail fence and pines to the east, nothing to the west.

Not a good location for G.P.S.

Came to the conclusion that the 1/2" iron pipe we found is the correct corner of said Section 32.

*E. Anderson*  
Edward E. Anderson  
P.S.#11495  
Professional Engineer  
STATE OF MICHIGAN  
LAND SURVEYOR & PROFESSIONAL ENGINEER  
NO. 11495