

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:10

For corners in
LIVINGSTON
(County)

Located in: TYRONE Corner Code #

9

HARCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- 1. Public Land Survey T 4N R 6E F-9
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

LSC# 1132m

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on SEPT. 28, 1999
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SET POST
8" Y. OAK N52E 58 LINKS (38.28')
16" W. OAK S19W 125 LINK (825')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD 4.5' SOUTH OF CENTERLINE GORDON ROAD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X30" PIPE WITH PLASTIC INSERT
CONNECTED TO A 1 1/4" X 6" PIPE WITH BRASS
CAP STAMPED "LIVINGSTON COUNTY
REMONUMENTATION CORNER
4.5' SOUTH OF THE CENTERLINE OF GORDON RD N16° W 22.45' SET REMON NAIL & TAG W/S 26"
N50°E 28.14' SET REMON NAIL & TAG SE/S TWIN OAK
OAK
S21°W 17.76' SET REMON NAIL & TAG NW/S 6"
CHERRY
N61°W 43.68' SET REMON NAIL & TAG SW/S 40"
OAK

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 5-19-99 CO. REP JED



Signed by [Signature] Date NOV. 9, 1999
Surveyor's Michigan License No. 29238