

FILED

JUL 14 9 46 AM '95

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILANI
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

corners in
Livingston
(County)

Located In: Corner Code #

Public Land Survey T 4N R 6E F-11

Property Controlling S _____ T _____ R _____

in Section S _____ T _____ R _____

Miscellaneous S _____ T _____ R _____

Property In Sec. S _____ T _____ R _____

L.S.C.#421m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Edward Anderson, in a field survey on June 6, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G.L.O. Notes dated: April 5, 1823
G.L.O. Witnesses: W. Oak 30" N82°E 48 Lks
W. Oak 30" S29°W 54 Lks

Additional historical data on back

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rerod. Fit witnesses by Boss, Albright, Anderson, and Richard Smith

CLERK OF COURT
LIVINGSTON COUNTY, MICHIGAN

OCT 11 1995

OCT 11 1995


Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 N 1/4 COR. SEC. 33 T4N-R6E

Set 1 1/4" x 36" iron pipe with brass cap (Liv. Co. Mon. Cor.)
13' - north of centerline of Faussett Road
N 08°E 22.69' Spike E/S 12" Elm
S25°W 49.26' Spike E/S 12" Hickory
S44°W 72.53' Spike W/S 12" Oak
N57°W 35.15' Spike S/S 12" Elm

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 5-3-95 CO. REP JED

signed by E. Anderson



Date July 5, 1995

Surveyor's Michigan License No. 11495



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

SUMMARY

April 27, 1995

F-11 N 1/4 CORNER SECTION 33, T4N-R6E, TYRONE TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" Rerod 13' \pm north of the centerline of Faussett Road (gravel)

Checked and measured to witnesses we found. Found 6 of 8 of Boss witnesses and they checked, pages 11, 12, and 20 this dossier. Found 2 of 3 of Albright witnesses, page 13 this dossier. Found 2 of 4 of Anderson witnesses and they checked, page 16 this dossier. Found 1 of 3 of Richard Smith witnesses and they checked, page 18 this dossier.

Distance from the N 1/4 corner to the N.E. corner of said Section 33 is 2649.20' on Richard Smith survey, page 17 this dossier, and 2648.98' on Anderson survey, page 16 this dossier, and 2649.12' on Boss survey, pages 15 and 19, this dossier.

Distance from the N 1/4 corner to the NW corner of said Section 33 is 2648.44' on Richard Smith survey page 17 this dossier, and 2648.45' on Albright survey, page 14 this dossier.

Made a clean sweep of immediate area and found no additional corner or irons.

Gravel roads running east and west. Roads are flat in both directions.

Terrain is wooded to the north and open to the south. House to the N.W., S.E., and S.W.

Tree line to the south.

Poor location for G.P.S.

Came to the conclusion that the 1/2" rion we found is the correct N 1/4 corner of said Section 33.

