

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>4</u> R <u>6</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

FILED
AUG 16 1 14 PM '94

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.#224m

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward E. Anderson in a field survey on August 2, ~~April 25~~, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NOTES Dated April 5, 1823
 G.L.O. WITNESSES B. Oak 18" S11°E 55 Lks
 B. Oak 24" N71°W 109 Lks

Deputy Surveyor Sylvester Sibley 1823-1825

ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

**SURVEY &
 REMONUMENTATION**

SEP 26 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe. No witnesses were available but checked within .05' to Section corner tag per G.L.O.


PA. 346 1980, APPROVED BY LIVINGSTON COUNTY PEER GROUP ON June 29, 1994, CO. REP [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 SW CORNER SECTION 34 T4N-R6E
 Set 1 1/4" x 36" Breakaway Iron Pipe with Brass Cap (Livingston County Monument Corner) in centerline Parshallville and 40' East of centerline of Hartland Road
 N20°E 44.78' Spike E/S 12" Twin Apple
 South 84.92' Spike W/S 12" Triple Maple
 S50°E 120.72' Spike E/S 30" Oak
 N43°W 78.24' Spike S/S 24" Oak
 West 83.11' 3/4" Bar

APPROVED BY LIVINGSTON COUNTY
 MONUMENTATION PEER GROUP
 JUNE 29, 1994

Signed by [Signature]
 Surveyor's Michigan License No. 11495



August 4, 1994



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

June 13, 1994

SUMMARY

G-13 S.W. CORNER OF SECTION 34, T4N-R6E, TYRONE TOWNSHIP
LIVINGSTON COUNTY, MICHIGAN.

Found 3/4" Pipe in centerline of Parshallville Road (gravel) and 40[±] East of
the centerline of Hartland Road (gravel)

Found no witnesses of record or in any of our Research.

Found 3/4" Bar 83.11' West of the S.W. corner and it checked close to
G.L.O. distance of 126 Links or 83.16'.

Distance from S 1/4 corner to the S.W. corner of said Section 34 is 2657.07'
as measured by E. E. Anderson on 6/7/94.

Distance from West 1/4 corner to the S.W. corner of said Section 34 is 2675.46'
on Alpha field notes, Page 8, this dossier.


Made a clean sweep of immediate area and found no other additional corners
or irons.

Terrain is open field to West. Fairly open to N.E. and slightly wooded
to S.E. House on N.E. corner.

Parshallville Road rises slightly to the East and flat to the West.

Hartland Road jogs to the west north of the intersection of Parshallville
Road and Hartland Road, and jogs back to the South about 40' west of
the S.W. corner of said Section 34.

Came to the conclusion that the 3/4" Pipe we found is the correct S.W.
corner of said Section 34.


Edward E. Anderson
P.S. #11495

