

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 NOV 22 A 11:10

For corners in
LIVINGSTON
(County)

Located in: TYRONE Corner Code #

9

HANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

- 1. Public Land Survey T 4N R 6E H-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____
Property in Sec. S _____ T _____ R _____

ISC# 1135m

Register of Deeds Stamp and File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Bryan L. Boss, in a field survey on SEPTEMBER 28, 1999
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

SET POST
10" W. OAK N87°E 55 LINKS (36.30')
4" W. OAK N25°W 14 LINKS (9.24')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 1/4" IRON PIPE FENCE POST IN CONCRETE AT FENCE
INTERSECTIONS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BRASS CAP STAMPED "LIVINGSTON COUNTY
REMONUMENTATION CORNER" IN TOP OF 2 1/4"
IRON PIPE FENCE POST IN CONCRETE AT FENCE
INTERSECTION
N25°E 1.75' SET REMON NAIL & TAG E/S 36" OAK
S59°E 22.98' SET REMON NAIL & TAG S/S 20" OAK
S10°W 18.64' SET REMON NAIL & TAG N/S 20" OAK
S63°W 22.22' SET REMON NAIL & TAG NW/S 26"
OAK



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
REC'D GROUP ON 6-16-99 CO. REP JED

Signed by [Signature] Date NOV. 9, 1999

Surveyor's Michigan License No. 29238