

FILED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

AUG 16 1 15 PM '94

For corners in

Livingston

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4 R 6 I-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.#229m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Edward E. Anderson in a field survey on August 3, ~~April 25,~~ 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NOTES Dated April 5, 1823
G.L.O. WITNESSES Ash 12" N64°E 25 Lks
W. Oak 12" S5°E 25 Lks

Deputy Surveyor Sylvester Sibley 1823-1825

ADDITIONAL HISTORICAL DATA ON BACK OF SHEET"

SURVEY &
REMONUMENTATION

SEP 26 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument 22" below surface of road. Fit location according to Plat of Lake Tyrone Estates #1, L.5, P 15 and 16.


P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY/
PEER GROUP ON June 1, 94 CO. REP [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 S.E. CORNER SECTION 34 T4N-R6E
Set 1 1/4" x 20" Breakaway Iron Pipe with Brass Cap (Livingston County Monument Corner) on top of monument at intersection of Holforth and Mabley Hill Roads
N60°E 59.00' Spike W/S 12" Elm
N25°W 65.85' Spike S/S Twin 6" Birch
S30°W 61.65' Spike E/S 12" Maple
S42°E 56.43' Spike W/S 8" Butternut

APPROVED BY LICINGSTON COUNTY
MONUMENTATION PEER GROUP
JUNE 1, 1994

Signed by [Signature]
Surveyor's Michigan License No. 11495



Date August 4, 1994



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

51 S. Leroy St.
Liveston, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

May 12, 1994

SUMMARY

I-13 S. E. CORNER SECTION 34, T4N-R6E, TYRONE TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN

Found concrete monument 22" below the Road Surface as called for on the recorded plat of Lake Tyrone Estates #1, L.5, P. 15 and 16, L.C.R., with an 18" 1/2" rerod on top of the monument bringing the top of the rerod to 4" below the surface of the intersection of the centerlines of Holforth Road (gravel) and Mabley Hill Road (gravel).

Checked and measured to witnesses we found. Found 3' of Garlock, Richard Smith, and Ray Phillips witnesses. They were all the same and they checked, Pages 8, 9, and 10, this dossier.

Distance from the South 1/4 to the S.E. corner of said Section 34 is 2655.37', Anderson calculations using the recorded plat of Lake Tyrone Estates #1, Liber 5, Pages 15 and 16, L.C.R., Pages 11, 12, 13, and 14, this dossier.

Distances from the East 1/4 corner to the S.E. corner of said Section 34 is 2676.00, Anderson calculations using the recorded plat of Lake Tyrone Estates #1, Liber 5, Pages 15 and 16, L.C.R., Pages 11, 12, 13, and 14 this dossier and 2675.81' Albright field notes, Page 7 this dossier.


Made a clean sweep of immediate area and found no additional corners or irons.

Terrain is fairly flat to North, South and East. Houses and Lake to West.

Mabley Hill Road (gravel) fairly flat to North and South. Holforth Road (gravel) is fairly flat to the East.

Came to the conclusion that the concrete monument we found is the correct S. E. Corner of said Section 34.

Edward E. Anderson
Edward E. Anderson
P. S. #11495



T4N R6E I-13 Page