

FILED

FILED

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

AUG 16 1 15 PM '94

AUG 16 1 15 PM '94

REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.#230m

Register of Deeds Stamp & File Number

For corners in

Livingston (County)

Located In:

Corner Code ##

- 1. Public Land Survey T 4 R 6 J-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 11, column J.

Edward E. Anderson in a field survey on August 5, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NOTES dated April 5, 1823
G.L.O. WITNESSES W. Oak 20" S50°W 120 Lks
W. Oak 6" N13°W 66 Lks
Deputy Surveyor Sylvester Sibley 1823-1825
ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

SURVEY & REMONUMENTATION
SEP 26 1994
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 8" Wooden fence corner post. Fit witnesses by Richard Smith P.S.

P.A. 346 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON June 1, 94 CO. REP. [Signature]


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11 N 1/4 CORNER SECTION 35, T4N-R6E
Corner falls in a 8" Wood Fence Corner Post
S69°W 27.27' 1" x 36" Iron Pipe with Brass Witness (L.C.R.W.) cap
N25°E 21.06' 1" x 36" Iron Pipe with Brass Witness (L.C.R.W.) cap
N54°E 23.25' 1"x 36" Iron Pipe with Brass Witness (L.C.R.W.) cap
S32°E 18.22' 1" x 36" Iron Pipe with Brass Witness (L.C.R.W.) cap
N79°W 27.10' Spike N/S 8" Oak
N27°W 27.87' Spike SE/S 8" Ash
N44°E 19.95' Spike SE/S 22" Oak
S41°E 15.82' Spike S/S 12" Oak

APPROVED BY LIVINGSTON COUNTY
MONUMENTATION PEER GROUP
JUNE 1, 1994

August 8, 1994

Surveyed by [Signature]
Surveyor's Michigan License No. 11495





EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

May 11, 1994

SUMMARY

J-11 N 1/4 CORNER SECTION 35, T4N-R6E, TYRONE TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN.

Found 8" wooden fence corner post with fence line running North, East, and West.

Checked and measured to witnesses we found. Found all of Richard Smith and all of Munsell and Garlock witnesses. They were the same. They checked. Pages 17, 18, and 19, this dossier.

Distance from N.E. corner to the North 1/4 Corner of said Section 35 is 2637.87' Munsell and Garlock, Pages 7, 8, and 13, this dossier.

Distance from N.W. corner to the North 1/4 corner of said Section 35 is 2666.76' Richard Smith, Pages 10 and 11, this dossier.

Made a clean sweep of immediate area and found no other corners or irons, except a 1/2" rerod (with Delta Engineering cap) at the South edge of the 8" wooden fence corner post. This iron did not check the witnesses by Munsell and Garlock and Richard Smith.

Found old fence line running North, East and West. Terrain is fairly flat and slightly wooded in all directions.

Came to the conclusion that 8" wooden fence corner post is the North 1/4 Corner of said Section 35.

Edward E. Anderson
P.S. #11495



T4N R6E J-11 P54