

SURVEY
REMONUMENTATION

FEB 25 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code //

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>4N</u> R <u>6E</u> | <u>K-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1998 OCT 22 P 1:17

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC948M

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bryan L. Boss, in a field survey on September 24, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post 1823
White Oak 8" N 43½ E 7 L
White Oak 6" S 68 W 22 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found ½" iron rod inside 1¼" pipe in mon box

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 8-5-98 CO. REP JED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1¼" by 30" pipe with 6" breakaway & Brass cap Stamped
"Livingston County Monumentation Corner" in existing monument box
N 20 E 56.73' set Remon N/T W/S 30" Oak
East 84.13 set Remon N/T S/S 24" Hickory
S 70 W 52.11 set Remon N/T N/S power pole
N 80 W 163.69 set Remon N/T S/S 24" Elm
East 31.90 found ½" iron rod capped



Signed by Bryan L. Boss

Date 10-12-98

Surveyor's Michigan License No. 29238