

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4 R 6 K-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

NOV 9 9 46 AM '93  
 NANCY HAVILAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

FILED

L.S.C.#40m

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward Anderson, in a field survey on August 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO DATE APRIL 5, 1823 / 8<sup>6</sup>  
 GLO WITNESSES B. Oak N64°E, 22 LKS  
 W. Oak 15" S78°W 34 LKS

ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" Iron fit Witnesses by Boss Engineering, Garlock (Professional Surveyor)  
 Cornerstone Engineering, Richard Smith (Professional Surveyor)


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SW Corner Section 36, T4N-R6E,  
 Set 1 1/4" x 36" Breadaway Iron Pipe with Brass Cap (Livingston County Monument Carrier) in Centerline of Holtforth Road.  
 N 80°E, 89.45' Spike S. side 30" Oak  
 S10°E, 46.68' N.W. Corner house Foundation  
 S50°W, 92.88' NE Corner Church Foundation  
 West 170.54' to R.R. Spike in Black Top Pavement (Fenton Road)

APPROVED BY LIVINGSTON COUNTY  
 MONUMENTATION PEER GROUP  
 OCTOBER 20, 1993

Signed by E. Anderson Date \_\_\_\_\_

Surveyor's Michigan License No. 11495





EDWARD E. ANDERSON, P.S., P.E.  
RICHARD F. FRANK, P.S.  
BRIAN R. SHALTZ, C.S.T.

Members of:  
Michigan Society of Professional Surveyors  
American Congress on Surveying and Mapping  
American Society of Civil Engineers

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

*Approved*

September 24, 1993

SUMMARY

K-13 S.W. CORNER, SECTION 36, T4N-R6E, TYRONE TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" capped iron in centerline gravel Road (Holtforth Road)

Cornerstone witnesses, Pages 12B and 24 this dossier. Found all witnesses and they field checked to the iron we found. Anderson and R. Smith witnesses, Pages 8, 15B, 17, and 22 this dossier. Found all witnesses and they field checked to the iron we found.

Boss and Garlock witnesses, Pages 9, 10, 18, and 23, this dossier. Found 3 witnesses; one was gone and they field checked to the iron we found.

Distances from S.W. corner to the West 1/4 corner of said 36 was 2669.25 per R. Smith, Page 17 this dossier, and 2669.43 per Boss, Pages 9 and 10 this dossier.

Distances from S.W. corner to South 1/4 corner of said 36 was 2655.43 per Anderson, and 40.32 chains or 2661.12' per Garlock, Pages 16 and 20, this dossier, and 2653.87 per Cornerstone Page ~~9A~~ <sup>17A</sup> this dossier.

Also found NW corner of Section 1, T3N-R6E, Hartland Township, Livingston County, Michigan (R.R. spike) in Blacktop road (Fenton Road) 3' - west of centerline, from witnesses by Kostecke and Tri-County, Pages 6 and 11, this dossier. Witnesses were all in and checked the R.R. spike we found. Measured the distance from the SW corner of said Section to the N.W. corner of said Section 1 and it measured 170.54' west of the iron we found at the S.W. corner of said Section 36; Garlock Page 19 this dossier shows 170.54; and G.L.O. calls for 264 links or 174.24'

Gravel Road (Holtforth Road) running East and West; No occupation to North or South; however, Black top Road (Fenton Road) begins curving to the East from the NW of said Section 1 at the intersection of Holtforth and Fenton Roads, and straightens out to the north in line with the SW corner of said Section 36.

Made a clean sweep of the immediate area and found no other irons or corners.

Terrain is fairly flat to East, West, North and South.

Came to the conclusion that the 1/2" iron we found was the correct S.W. Corner of said Section 36.

*E. Anderson*  
Edward E. Anderson,  
P.S. #11495