

DEC 13 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
LIVINGSTON  
(County)

Located In:	Corner Code #/
T <u>4</u> R <u>6</u>	<u>L-13</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

NANCY HAVILLAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48893

NOV 9 9 46 AM '93

FILED

L.S.C.#42m

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Edward Anderson, in a field survey on August 20, 1993,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO NOTES DATED APRIL 5, 1823  
GLO WITNESSES W. Oak 15" S40°E, 28 LKS  
W. Oak 12" N11°W, 29 LKS

ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" x 18" Iron fit Witnesses by Cornerstone Engineering, Boss Engineering,  
Garlock (Professional Surveyor), E. E. Anderson & Assoc.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 SOUTH 1/4 Corner Sec 36, T4N-R6E  
SET 1 1/4" x 36" Breakaway Iron Pipe with Brass Cap (Livingston Co. Mon. Cor.)  
in centerline of Holtforth Road.  
N65°W 63.94' Spike E/S 28" Oak  
N15°W 42.52' Spike E/S 18" Wild Cherry  
N45°E 42.74' Spike E/S 14" Oak  
West 72.35' to 1/2" iron in Roadbed

APPROVED BY LIVINGSTON COUNTY  
MONUMENTATION PEER GROUP  
OCTOBER 20, 1993

Signed by Edward Anderson  
Surveyor's Michigan License No. 11495



Date November 2, 1993

401 S. Leroy St.  
Fenton, Michigan 48430-2164

(313) 629-8974  
FAX (313) 629-9069

*approved.*

September 24, 1993

SUMMARY

L-13 SOUTH 1/4 CORNER, SECTION 36, T4N-R6E, TYRONE TOWNSHIP,  
LIVINGSTON COUNTY, MICHIGAN

Found 1/2" iron in centerline gravel road (Holtforth Road)

Cornerstone witnesses, Pages 9B and 15, this dossier. Found all witnesses,  
and they field checked to the iron we found.

Anderson, Boss, and Garlock witnesses, Pages 6B, 7, 8B, 11B, 12 and 14, this  
dossier. Found one witness to the north; witnesses to the south were  
gone. Witness to the north field checked to the iron we found. Measured  
from iron we found at S 1/4 Corner to the SE corner of Parcel 6 (that  
we found); Boss survey Page 6A this dossier. Measured distance checked  
within 0.14 of distance shown on said Boss survey.

Distances from S 1/4 corner to S.W. corner of said Section 36 was 2653.87 per  
Cornerstone, Page 9A this dossier and 2655.43 per Anderson, Page 11A this  
dossier and 40.32 chains equals 2661.12 per Garlock, Page 13, this dossier.

Distances from S 1/4 corner to the S.E. corner of said Section 36 was  
2679.52 per Boss, Pages 6A and 7, this dossier and 40.25 chains = 2656.50'  
per Garlock Page 13 this dossier.

Also, found the N 1/4 of Section 1, T3N-R6E, Hartland Township, Livingston  
County, Michigan (1/2" iron) by rough measurement to the west (using 1/2  
the distance of the jog at the S.W. of said 36) and found a 1/2" iron  
at the N 1/4 corner of said Section 1, and the distances between the  
S 1/4 of said 36 and the N 1/4 corner of said Section 1 measured 72.35'.

Gravel road (Holtforth Road) running East and West. No occupation to the  
south. Found an old fence line running to the north.

Made a clean sweep of the immediate area and found no other irons or  
corners.

Terrain is fairly flat North, South, East, and West. Corn field to the  
south and heavy woods to the north.

Came to the conclusion that the 1/2" iron we found was the correct S 1/4  
corner of said Section 36.

*E. Anderson*  
Edward E. Anderson  
P.S. #11495

