

SURVEY & REMONUMENTATION

DECEMBER 3 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 9 9 46 AM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48043

FILED

For corners **COMMISSION**

LIVINGSTON
 (County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|----------|---|----------|-------------|
| 1. Public Land Survey | T | <u>4</u> | R | <u>6</u> | <u>M-12</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |

L.S.C.# 44m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward Anderson, in a field survey on August 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO NOTES DATED APRIL 5, 1823
 GLO WITNESSES W. OAK 8" N45°W 27 LKS
 W. OAK 14" S18°W, 87 LKS

ADDITIONAL HISTORICAL DATA ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" x 18" Iron Road. Fit Witnesses by Alpha Engineering and Boss Engineering.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 E 1/4 CORNER SEC 36, T4N-R6E
 Set 1 1/4" x 36" Bredaway Iron Pipe with Brass Cap (Livingston Co. Monument Corner) 3' West of Centerline of Tipsico Lake Road.
 N 40°E 37.79' Spike W/S 24" Twin Oak
 S 55°E 40.24' Spike N/S 10" OAK
 S75°W 15.21' Spike N/S 26" Oak
 N65°W 24.29' Spike S/S 12" Oak

APPROVED BY LIVINGSTON COUNTY
 MONUMENTATION PEER GROUP
 OCTOBER 20, 1993

Signed by Edward Anderson
 Surveyor's Michigan License No. 11495



Date November 2, 1993



EDWARD E. ANDERSON, P.S., P.E.
RICHARD F. FRANK, P.S.
BRIAN R. SHALTZ, C.S.T.

Members of:
Michigan Society of Professional Surveyors
American Congress on Surveying and Mapping
American Society of Civil Engineers

401 S. Leroy St.
Fenton, Michigan 48430-2164

(313) 629-8974
FAX (313) 629-9069

approved.

September 24, 1993

SUMMARY

M-12 EAST 1/4 CORNER, SECTION 36, T4N-R6E, TYRONE TOWNSHIP,
LIVINGSTON COUNTY, MICHIGAN

Found 1/2" iron in Gravel Road (Tipsico Lake Road) 3'[±] west of centerline.

Alpha witnesses, Page 9 this dossier. Found all witnesses and they field checked to the iron that we found. Boss witnesses, Page 10 this dossier. Found all witnesses and they field checked to the iron that we found.

Looked for iron at the West 1/4 corner of Section 31, T4N-R7E, Rose Township, Oakland County, Michigan, by rough measuring to the south 1/2 the G.L.O. jog at the N.E. of said Section 36, and found nothing or no occupation to the east.

Distances from the East 1/4 corner to the SE corner of said Section 36 was 2672.21 per Boss, Pages 6A, and 6B, this dossier; and 40.11 1/2 chains equals 2647.59' per Garlock, Page 12, this dossier.

Distances from the East 1/4 corner to the NE corner of said 36 was 2698.98 per Alpha Engineering, Page 8 this dossier, and 40.11 1/2 chains equals 2647.59 per Garlock Page 12 this dossier.

Gravel Road (Tipsico Lake Road) North and South. Found old fence to West. Found no occupation to East.

Made a clean sweep of the immediate area and found no other irons or corners.

Terrain fairly flat East, West, and South. Rises to the North. Swampy to the East and West.

Came to the conclusion that the 1/2" iron we found was the correct East 1/4 corner of said Section 36.

E. Anderson
Edward E. Anderson
P.S.# 11495

Architectural, Construction, Property and Drainage Surveys
Civil Engineering • Land and Site Planning • Mortgage Inspection Reports