

SURVEY & REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in
Livingston
(County)

Located In: Corner Code #

2000 NOV 15 A 9:29

- 1. Public Land Survey T 4N R 6E K-10
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property In Sec. S _____ T _____ R _____

NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

LSC #1363m
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ed Anderson, in a field survey on 10-18, 19 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


K-10 Found Railroad Spike

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 9-6-00 CO. REP JED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-10 West 1/4 corner Section 25, T4N-R6E**
- Set 1 1/4" x 36" Iron Pipe w/Brass Cap (Liv. Co. Mon. Cor.)**
- S 40° E, 73.92' Northwest corner of porch 2' above ground
- S 70° W, 62.90' Set Nail and Liv. Co. Remon Tag in North face 20" Hickory
- N 40° E, 66.19' Set Nail and Liv. Co. Remon Tag in West face 22" Elm
- N 50° W, 54.82' Set Nail and Liv. Co. Remon Tag in South face Power Pole

Signed by Ed Anderson
 Surveyor's Michigan License No. 11119



Date 10/19/00