

SURVEY & REMONUMENTATION

OCT 1 1 1994

COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 40N R 4W D-1 ✓
T 41N R 4W D-13
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

RECEIVED & FILED
DIANE FRAL KOVICH
MACKINAC COUNTY REGISTER OF DEEDS

SEP 6 1994
AM _____ PM _____
7/8/9/10/11/12/13/14/15/16/17/18/19/20/21/22/23/24/25/26/27/28/29/30/31

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Neil E. Hill, in a field survey on August 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set wood post
Tied 12" Cedar N34E 0.26 chains
7" Cedar N17W 0.11 chains

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94
James H. Granger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1974 found wood post by Glen A Bergey; recorded Liber A, Page 131.
1978 found and tied by MDOT
1982 found and tied by Bill Karr
Fourth correction line run by USFS
1994 found brass capped, stamped, concrete monument
14" Cedar N20W 0.20 ch 10" Cedar N61E 0.21 ch
8" Cedar S07E 0.26 ch 8" Cedar S53E 0.35 ch

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted corner in its current location.
Accepted the USFS witnesses as follows:
14" Cedar N20W 13.20' 10" Cedar N61E 13.86'
8" Cedar S07E 17.16' 8" Cedar S53E 23.10'



Signed by Neil E. Hill P.S. Date August 22, 1994

Surveyor's Michigan License No. 27447

D-0270

09-06-94 10L3183

MSSR

09-06-94
10L3183
MSSC