

**SURVEY &  
REMONUMENTATION**

OCT 11 1994

COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac  
(County)

Located In:

Corner Code #

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>40N</u> R <u>4W</u> | <u>D-3</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

SEP 6 1994  
AM \_\_\_\_\_ PM \_\_\_\_\_  
7/8/9/10/11/12/13/14/15/16

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Neil E. Hill, in a field survey on August 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- Set post Mullett 1845  
10" Beech N83E 0.22 ch  
20" Birch S33W 0.22 ch



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1973 Wood post found by Bergery and replaced ; Recorded Liber A, Page 85.  
1978 Found & tied by MDOT  
1982 Used by MDOT, Liber B, page 380  
1988 Used by MDOT in division of Section 5  
1994 Found Brass capped stamped monument  
8" Beech East 0.28 ch 6" Maple N75W 07.86'  
13" Beech S04E 0.49 Ch 11" Beech Due East 18.61'  
9" White Ash N80W 0.54 ch 4" Maple S30E 08.29'  
6" Beech N19E 0.52 ch

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Accepted corner by USFS.  
Accepted the following witnesses:  
8" Beech East 18.48' 6" Maple N75W 07.90' (MDOT tag)  
13" Beech S04E 32.34' 11" Beech Due East 18.61' (MDOT tag)  
9" White Ash N80W 35.64' 4" Maple S30E 08.24' (MDOT tag)  
6" Beech N19E 34.32'

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 8-16-94

Signed by Neil E. Hill P.S. Date August 22, 1994

Surveyor's Michigan License No. 27447