

SUPERVISOR  
 REMONUMENTATION  
 APR 10 1995  
 COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac  
 (County)

Located In: \_\_\_\_\_ Corner Code 77

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>40N</u> R <u>4W</u> | <u>E-2</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

**RECEIVED & FILED**  
 DIANE FRANKOVICH  
 MACKINAC COUNTY REGISTER OF DEEDS

NOV 09 1994  
 AM \_\_\_\_\_ PM \_\_\_\_\_  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Neil E. Hill, in a field survey on October 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post Burt  
 20" Birch N49W 0.50 ch  
 8" Sugar Maple S49E 0.30 ch  
 Feindt in area computed location  
 1978 MDOT found and tied  
 1982 MDOT subdivided section  
 1988 Various surveys since then  
 1994 No witnesses of record, center recorded Liber B, Page 405.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod with cap by Charlevoix #24599 & #28424, half-way and on line between the N Corner and the SW Corner. Also found 3/4"x3/4"x18" iron believed by T.L. Jackson S45E 9.00'. Accepted 1/2" re-rod as 1/4 corner.

ACCEPTED BY THE MACKINAC COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 10-17-94

*James H. Kranger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" re-rod. Replaced with 5/8" re-rod with 4" aluminum cap.  
 Set following witnesses:  
 16" Maple N80W 22.51' (MDOT tag)  
 12" W. Birch S20E 15.53' (MDOT tag)  
 18" W. Birch S85E 35.63'  
 8" Maple S20W 7.63'



Signed by Neil E. Hill PS Date October 17, 1994

Surveyor's Michigan License No. 27447