

**SURVEY & REMONUMENTATION**

OCT 11 1994

COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECEIVED & FILED**  
DIANE FRAT KOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

SEP 6 1994  
AM \_\_\_\_\_ PM \_\_\_\_\_  
7|8|9|10|11|12|13|14|15|16

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Neil E. Hill

August 22, 1994

I, Neil E. Hill, in a field survey on August 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post  
Tied 6" Birch N42W 0.31 ch  
12" Sugar S30E 0.41 ch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1982 MDOT found & tied; recorded Libre B, Page 379  
1994 Found 1" iron pipe  
14" Beech N30W 31.93'  
9" Beech N05W 37.91'  
6" W. Birch S05W 26.01'  
7" Beech S35E 28.90'

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-16-94

*James H. Kravger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted location of 1" pipe.  
Placed 5/8" re-rod with 4" aluminum cap inside of 1" pipe.  
Accepted witnesses of record:  
14" Beech N30W 31.93'  
9" Beech N05W 37.91' (dead)  
6" W. Birch S05W 26.01'  
7" Beech S35E 28.90'



Signed by Neil E. Hill P.S. Date August 22, 1994  
Surveyor's Michigan License No. 27447

09-06-94

FILED  
M.S.C.