

**SURVEY & REMONUMENTATION**

OCT 1 1 1994

COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac  
(County)

Located In:

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>40N</u> R <u>4W</u> | <u>E-5</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

RECEIVED & FILED  
DIANE FRANKOVICH  
REGISTER OF DEEDS

AM SEP 6 1994 PM  
7/8/9/10/11/12/13/14/15/16

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Neil E. Hill, in a field survey on August 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set post 1845  
Tied 12" Birch S70W 0.70 ch  
No other

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No record of this corner on the ties of Supervisor's Plat No. 1 of Moran Township, April 14, 1930.  
Located plat monument on South side of Gros Cap Road; also located monumentation on North side of Gros Cap Road to the West.

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 8-16-94

*James H. Shanger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" re-rod with 4" aluminum cap at P.O.B. location of Supervisors Plat No. 1 of Moran Township.
- |           |      |       |            |
|-----------|------|-------|------------|
| 8" Cedar  | S50W | 49.27 | (MDOT tag) |
| 14" Cedar | S35W | 43.65 | (MDOT tag) |
| 12" Cedar | S05W | 56.54 | (MDOT tag) |
| 6" Cedar  | S05E | 56.72 | (MDOT tag) |



Signed by Neil E. Hill P.S. Date August 22, 1994

Surveyor's Michigan License No. 27447

b-0276

09-06-94 1CL3183

MSSR

2

09-06-94  
1CL3183  
FILED  
Mise