

SURVEY
REMONUMENTATION

MAY 20 1997

COMM

MACKINAC COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 40N R 4W F-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV 15 1996
AM _____ PM _____
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

U.S.F.S. 2649.03' 2648.18' U.S.F.S.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Neil E. Hill, in a field survey on SEPTEMBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes. Set 1/4 post.

- 6" Beech N59E 16 lks
- 12" Beech N71W 8 lks

Recorded Liber B, Page 326.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found F.F.S. std. corner. 2 1/2" X 5' concrete filled galvanized iron pipe, 3/5' in ground with 3" brass tablet.

- 11" Maple S31E 12.3'
- 6" Maple N42W 17.4'
- 9" Maple S57W 3.8'

Cedar post, East 3.4' with monument sign attached.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 9-30-96


James H. Strayer

Also recorded in: T41N, R4W, F-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted corner as found

- 12" Maple S31E 12.30 (nail)
- 8" Maple N42W 17.40 (tag side)
- 10" Maple S57W 3.81 (tag side)
- 14" Maple N70E 4.96 (nail)



Signed by Neil E. Hill P.S. P.C. Date _____

27447

SEPTEMBER 30, 1996

Surveyor's Michigan License No. _____

E 0083