

SURVEY & REMONUMENTATION

MAR 13 1998 MACKINAC COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>F-3</u>
	T _____ R _____	<u>1/4 Cor common</u>
	T _____ R _____	<u>to Sec's 4 & 9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED & FILED
DIANE FRAP KOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997
AM _____ PM _____
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Neil E. Hill, in a field survey on DECEMBER 22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1845 GLO notes William Burt 10" Cedar for 1/4 post
1982 N. Hill, MDOT Found cedar post; Set 1" iron pipe, recorded Liber B, Page 381

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 Found 1" iron pipe (Old witnesses)
14" Spruce S45W 12.88 feet
12" Cedar S05E 18.10 feet
13" Spruce N80E 22.37 feet
10" Cedar N20W 21.85 feet

Accepted corner location.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997 Found 1" iron pipe. Set 1/2" rerod with remonumentation cap inside found pipe.
16" Spruce (dead) S45W 12.94' MDOT Tag
14" Cedar S05E 18.19' MDOT Tag
16" Spruce N80E 22.47' New Nail
12" Cedar (leaning) N10W 21.45' MDOT Tag



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997

Surveyor's Michigan License No. 27447