

SURVEY & REMONUMENTATION

MAY 20 1997

COMMISSION

**MACKINAC COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>G-1</u>
	T. R.	
	T. R.	<u>Sec. cor common to</u>
	T. R.	<u>Sec.'s 3-4-33-34</u>
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV 15 1996
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

45.75 2648.10' 2652.44' 45.75.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Neil E. Hill, in a field survey on SEPTEMBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes. Set corner post.

- 8" Cedar N55E 19 lks
- 8" Cedar N34 1/2 W 33 lks

Scribed wood post.

Recorded Liber B, Page 327.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found F.F.S. std. corner.

2 1/2"x5' concrete filled galvanized iron pipe, 3.2' in ground with 3" brass tablet.

- 9" Cedar N51E 16.2'
- 12" Cedar S84E 21.4'
- 12" Cedar S16W 38.0'
- 9" Cedar N21W 6.0'

Cedar post, N10W, 1.8' with monument sign.

Accepted corner location

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-30-96

James H. Granger

Also recorded in: T 41N, R4W, G-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted corner location as found. Measurements to nails in side of trees.

- 12" Cedar N51E 16.23'
- 14" Cedar S16W 38.02'
- 14" Cedar S84E 21.39'
- 11" Cedar N21W 6.05'

Woods to the West and South and a clearing to the NE.



Signed by Neil E. Hill P.S. P.C. Date SEPTEMBER 30, 1996

Surveyor's Michigan License No. 27447

E 0034