

SURVEY & REMONUMENTATION

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED
 DIANE PRAT KOVICH
 MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997
 AM PM
 7|8|9|10|11|12|1|2|3|4|5|6

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>G-2</u>
	T _____ R _____	<u>1/4 Cor common</u>
	T _____ R _____	<u>Sec's 3 & 4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Neil E. Hill, in a field survey on DECEMBER 22 97, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1845 GLO notes William Burt 8" Sugar N66E 11 lks
 10" Beech S85W 21 lks

No records of this corner being perpetuated


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 No evidence of corner.
 Set midway and on line between Section Corners North & South.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-22-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" re-rod and remonumentation cap.
 14" Poplar Due West 21.01'
 12" Birch N55W 18.25'
 14" Triple W. Birch N25E 34.33'
 6" Oak N85E 33.77'



DECEMBER 22, 1997

Signed by Neil E. Hill P.S. Date _____
 Surveyor's Michigan License No. 27447