

MAY 20 1997

COMMISSION MACKINAC COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac (County)

Located In:

Corner Code #

- 1. Public Land Survey T 40N R 4W H-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

RECEIVED & FILED DIANE FRANKOVICH MACKINAC COUNTY REGISTRAR OF DEEDS

NOV 15 1996 AM PM 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

2652.44 U.S. F.S.

Grid table with columns A-M and rows 2-13. Cell G4 contains a dot representing a corner point.

I, Neil E. Hill, in a field survey on SEPTEMBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

U.S.F.S.

Corner position was re-established by single proportionate measurement between recovered corners to the east & west.

G.L.O. notes. Set 1/4 post.

- 7" Tamarack N55E 19 lks
5" Tamarack N62W 11 lks

Recorded Liber B, Page 338.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found F.F.S. std. corner. 2 1/2" x 5' concrete filled galvanized iron pipe, 3.8' in ground with 3" brass tablet

- 7" Cedar N88E 67.3'
4" Cedar S01E 16.3'
8" Cedar N30W 30.0'

Cedar post, West 2.5' with monument sign.

Accepted corner location.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 9-30-96

James H. Branger

Also recorded in: T 41N, R4W, H-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted corner as found. Measurements to nails in side of trees.

- 10" Cedar N88E 67.42'
6" Cedar S01E 16.24'
11" Cedar N30W 29.85'
4" Cedar N55E 09.08'



Signed by Neil E. Hill P.S., P.C. Date SEPTEMBER 30, 1996

27447

Surveyor's Michigan License No.