

SURVEY & REMONUMENTATION

MAR 13 1998 MACKINAC COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Mackinac
(County)

Located In:

Corner Code 44

- | | | |
|------------------------------------|--------------------------|----------------------------|
| 1. Public Land Survey | T <u>40N</u> R <u>4W</u> | <u>H-3</u> |
| | T _____ R _____ | <u>1/4 Cor common</u> |
| | T _____ R _____ | <u>to Sec's 3 & 10</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997
AM
7 8 9 10 11 12 13 14 15 16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Neil E. Hill, in a field survey on DECEMBER 22 97, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1845 GLO notes William Burt 8" Cedar S41E 7 lks
 6" Fir N41W 12 lks
 No records of this corner being perpetuated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 Found no evidence of corner. Set midway and on line between Section Corners East & West.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" rod with remonumentation cap.
 5" Cedar Due North 13.42'
 7" Cedar S80E 25.61'
 4" Tamarack S15W 05.08'
 6" Cedar S75W 15.03'



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997
 Surveyor's Michigan License No. 27447