

**SURVEY & REMONUMENTATION**

**MACKINAC COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE**

APR 10 1995  
 Meeting Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

or corners in  
Mackinac  
 (County)

Corner Code #

**RECEIVED & FILED**  
 DIANE FRAT KOVICH  
 MACKINAC COUNTY CLERK OF DEEDS

NOV 09 1994  
 AM PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

Public Land Survey T 40N R 4W H-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

Neil E. Hill October 3, 1994

in a field survey on \_\_\_\_\_, 19\_\_\_\_\_,  
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5							●					
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Set 4" cedar post at 40 ch.  
 No witnesses  
 The GLO notes differ from the GLO map.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No record of this corner.  
 Set the South 1/4 Corner at pro-rated GLO distance for the South 1/4 Corner of Section 10. The  
 GLO notes for this location were used to re-set this corner.  
 See back for corner locations along Section Line.

ACCEPTED BY THE MACKINAC COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELDON 10-17-94

*James H. Sherrin*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard FFS monument at this location.  
 18" Cedar N65W 07.55'  
 8" Cedar N60E 20.09'  
 12" Cedar S40E 30.18'  
 12" Cedar S10E 25.61'



Signed by Neil E. Hill P.S. Date October 17, 1994  
 Surveyor's Michigan License No. 27447

11-09-94 1CL4245 MISC

**SURVEY &  
REMONUMENTATION  
COMMISSION**  
APR 10 1995

Moran Township, Mackinac County, Michigan

Section 10 T40N, R4W

GLD Notes 3579.18' 3522.84'

Witnesses #15 Sec. 10

- 6" P. Pine N75E 07.05'
- 4" I. Pine S70E 14.18'
- 5" Cedar N25E 13.22'
- 8" Cedar S75W 22.45'

S 1/4 Cor. Sec. 10  
Set std. FFS monu.  
Gout. Lot #2

#15 Sec. 10  
Set 1/2 Re-rod  
w/ cap #27147

SW 1/4 of SW 1/4

marker corner

marker in Moran River

99.1%

1299.22'

1524.03'

Gout. Lot #8

SE 1/4 of SE 1/4

1299.22'

1324.94'

NE 1/4 of NW 1/4

Property Controlling Gout. Lot #1

N 1/4 Cor. Sec. 15

Set Sta. County Monu.

5/8" re-rod w/ 4" minimum cap

924.40'

673.87'

Set std. County monu.

North line of adjacent

State # 6

West claim line

Gout. Lot #8

#1 Sec. 15  
Set 1/2 re-rod w/ cap #27147

- 20" Norway Pine N80W 17.30'
- 8" Cedar N50W 01.36'
- 10" Cedar S35E 20.45'
- 5" Cedar N85E 47.04'

Section 15 T40N, R4W

GLD Map 3313.20'

indicates Gout. Lot #1  
North Line 673.20' GLD