

**MACKINAC COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac
(County)

Located In:

Corner Code #

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTRE OF DEEDS

NOV 15 1996

AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

1. Public Land Survey T40N R4W I-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Neil E. Hill, in a field survey on SEPTEMBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes. Set 1/4 post.

- 4" Cedar N34E 18 lks
- 6" Cedar S69W 17 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of corner.

Set 1/4 Corner at single proration between section corners to the North and South.

SURVEY &
REMONUMENTATION

MAY 20 1997

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-30-96

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" roerd with 4" aluminum cap.

- 12" Cedar North 12.52'
- 12" Cedar N45E 8.12'
- 16" Cedar S85E 16.59'
- 8" W. Birch S35W 6.46'



Signed by Neil E. Hill S.S., P.C. Date SEPTEMBER 30, 1996

27447

Surveyor's Michigan License No. _____