

SURVEY & REMONUMENTATION

OCT 11 1994

**MACKINAC COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #/

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>40N</u> | R | <u>4W</u> | <u>I-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

RECEIVED & FILED
DIANE FRAT KOVICH
MACKINAC COUNTY REGISTER OF DEEDS

SEP 6 1994

AM 7:18 PM 7/8/94

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Neil E. Hill

August 22

94

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Set post 12" Cedar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1974 Feindt used corner recorded Liber A, page 137
1978 MDOT tied and used corner

1994 Found 1" iron pipe

6" Fir	S27E	15.15'	(gone)
8" Cedar	N34E	03.35'	
10" Spruce	N27W	07.70'	

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-16-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 1" pipe; placed 5/8" re-rod inside pipe with 4" aluminum cap.

8" Cedar	N34E	04.06'	(nail in side)
12" Spruce	N27W	07.75'	(nail in side)
12" Cedar	N30E	10.62'	(nail in side)
4" Fir	S55W	08.83'	



Signed by Neil E. Hill P.S. Date August 22, 1994

Surveyor's Michigan License No. 27447

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

09-06-94 1CL31B3

REGISTERED