

SURVEY & REMONUMENTATION

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|--------------------------|----------------------------|
| 1. Public Land Survey | T <u>40N</u> R <u>4W</u> | <u>J-3</u> |
| | T _____ R _____ | <u>1/4 Cor common</u> |
| | T _____ R _____ | <u>to Sec's 2 & 11</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED & FILED
DIANE PRAT KOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997
AM PAM
7|8|9|10|11|12|13|14|15|16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										•			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Neil E. Hill

DECEMBER 22 97

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1845 GLO notes William Burt 10" Cedar S11W 4 lks
4" Tamarack N30W 6 lks

No records of this corner being perpetuated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 No evidence of corner. Set midway on line between Section corner West and theoretical location of Section corner East in Chain Lake.

THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER PA. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" rerod with remonumentation cap.

- 5" Cedar S80E 16.96'
- 6" Cedar S25W 04.21'
- 6" Cedar N45W 07.20'
- 5" Cedar N15E 06.60'



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997
Surveyor's Michigan License No. 27447