

**MACKINAC COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>K-1</u>
	T _____ R _____	
	T _____ R _____	Sec. cor common to
	T _____ R _____	sec.'s 1-2-35-36
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV 15 1996
AM _____ PM _____
7|8|9|10|11|12|13|14|15|16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2452.44' 46.85' 7457.52' 43

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Neil E. Hill, in a field survey on SEPTEMBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes. Set sec. cor. post
16" Cottonwood N25E 23 lks
12" Birch N53W 22 lks
From survey of Section 36 by C.A.&E. 1977.

Recorded on U.S.F.S. Plat drawing.

SURVEY &
REMONUMENTATION
MAY 20 1997
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe.
4" Balsam S40W 10.9'
5" Poplar S40E 8.0'
3" Poplar N60E 7.4'
6" Poplar N10W 18.9'

Accepted corner location.

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-30-96

James H. Kranger

Also recorded in: T 41N, R4W, K-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 5/8" rerod with 4" aluminum cap inside found 1" iron pipe.

12" Poplar N25W 14.86'
10" Poplar S35E 8.32'
10" Poplar S10E 10.56'
10" Balsam S40W 11.20'

Measurements to nails in side of trees.
Road to North and East.



Signed by Neil E. Hill P.S., P.C. Date SEPTEMBER 30, 1996
Surveyor's Michigan License No. 27447