

SURVEY & REMONUMENTATION

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTRAR OF DEEDS

DEC 29 1997

AM PM
7|8|9|10|11|12|1|2|3|4|5|6

For corners in

Mackinac
(County)

Located In:

Corner Code #/

- | | | | | | |
|------------------------------------|---|------------|---|-----------|---------------------------|
| 1. Public Land Survey | T | <u>40N</u> | R | <u>4W</u> | <u>K-2</u> |
| | T | | R | | <u>1/4 Cor common</u> |
| | T | | R | | <u>to Sec's 1 & 2</u> |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Neil E. Hill

DECEMBER 22 97

I, Neil E. Hill, in a field survey on DECEMBER 22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845 GLO notes William Burt 18" Birch N37W 40 lks
20" Birch S61E 38 lks
1975 Section work in Section 12 by Jerry Wilcox
1980's Section work by M. Feindt & U.S.F.S.
1986 Corner set by N. Hill recorded Liber B, page 146

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 Found 3/4" pipe with cap #27447. (Old witnesses)
18" W. Birch Due West 37.44 feet
6" Maple N40E 06.25 feet
8" W. Birch S20E 07.30 feet
8" W. Birch N65W 14.58 feet

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

Computed Section breakdown indicates this corner should have been set 3.26' North of found location. Did not accept corner location, set at new computed location midway and on line between Sec. Corner North & computer Section corner in Chain Lake to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 1/2" re-rod and remonumentation cap.
8" Birch Stump Due West 06.22'
6" Maple N60E 04.60'
14" W. Birch N5W 34.21'
5" W. Birch S25E 20.25'
3/4" Pipe Due South 03.26'



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997
Surveyor's Michigan License No. 27447