

SURVEY & REMONUMENTATION

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40N</u> R <u>4W</u>	<u>L-3</u>
	T _____ R _____	<u>1/4 Cor common</u>
	T _____ R _____	<u>to Sec's 1 & 12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Neil E. Hill, in a field survey on DECEMBER 22 97, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1845 GLO notes William Burt 12" Cedar N42W 36 lks
 16" Birch S60W 22 lks
 1975 Jerry Wilcox found 3/4" square headed bolt, recorded in Liber A, page 185

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 Found 3/4" square headed bolt (Old witnesses)
 5" Maple S30E 20.15 feet
 5" Cedar S05W 31.96 feet

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1997 Found 3/4" square headed steel rod 12" in length removed. Set 1/2" reroed with remonumentation cap.
 14" Spruce S80E 25.19'
 20" Spruce S75W 28.87'
 10" Maple S30E 20.03'
 6" Cedar S35W 31.98'



Signed by Neil E. Hill P.S. Date _____
 Surveyor's Michigan License No. 27447

DECEMBER 22, 1997