

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Lackinac COUNTY


T 41a R 11W

DESCRIPTION OF CORNER Meander Corner bet. Secs. 7-8 on shore of Lake Michigan

CORNER MONUMENT 1" pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/25/69

WITNESSES TO CORNER..... 12" Y. Pine (N.C. MBT) S22°W 25.2'



10" Y. Pine (N.C. MBT) N23°E 16.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from possible witnesses. Found remains of W. Pine Stump bearing $S70^{\circ}E$. 26LKS. and also fragments of W. Pine Stump bearing $N47^{\circ}W$. 37LKS. These fragments have blazes and what appears to be witness marks.

Position checks well with Sec. Cor. to North; stream to east and meanders of the lake shore.

SURVEYOR'S SEAL

Billy D. Buckler

SIGNED

Billy D. Buckler

DATE

6/23/72

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68