

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Mackinac COUNTY  
T 41N R 11W

DESCRIPTION OF CORNER Meander Corner, bet. Secs. 9-10, on the shore of Lake Michigan

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 9-18-69

WITNESSES TO CORNER..... 7" Cedar (NBT) N73°W 5.2'



9" Cedar (NBT) N37°E 8.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This monument placed as a Meander Cor., on the Section Line but North of the original Meander Corner position.  
Monument placed in the timber edge and on a very old line of blazes, which we found running South from the Sec. Cor. 3-4-9-10.  
Corner placed 1,035.0' South of Sec. Cor.  
Record Distance - 1043.0'  
Found no evidence of original corner or Tamarack witness.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE

9-24-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68