

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES


LAND CORNER RECORD

Mackinac COUNTY  
T 41N R 11W

DESCRIPTION OF CORNER ¼ Corner bet. Secs. 4-9  
CORNER MONUMENT 1" pipe with 4" Aluminum Cap  
DATE MONUMENT PLACED AND WITNESSED 4/6/72  
WITNESSES TO CORNER.....

12" W. Pine (¼s NBT) S48°E 55.3'

8" Cedar (¼s NBT) N15°E 65.2'



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old squared post, set by unknown Surveyor.

Found no evidence of original witnesses which were; W. Pine 6" S39°E 60 Links and  
W. Pine 4" S30°W 39 Links.

Corner lies in small open marsh. Found a 5" Cedar with a blaze and notch facing corner.  
These marks are of indeterminate age, bearing S86°E 49.2'.

SURVEYOR'S SEAL

*Billy D. Buckler*

DISTRIBUTION:

SIGNED Billy D. Buckler DATE 5/23/72  
REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68