

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

MacKinac COUNTY


T 41N R 11W

DESCRIPTION OF CORNER West 1/16 Corner bet. Secs 4-9

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/6/72

WITNESSES TO CORNER..... 8" Cedar (w/1/16 bt) N28°E 16.4'



7" Cedar (w/1/16 BT) N50°W 14.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed midway and on line bet. Sec. Cor. to West and 1/4 Cor. to East.

Found a squared wood post, 1.0' East of this location as well as an iron fence post and a wood post, 5.0' East and 6.0' South of this location.

Corner lies in Cedar Swamp.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

Billy D. Buckler

DATE

6/25/72

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68