

18

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 11W	D1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 5 T 41N R 11W	1
	S 5 T 41N R 11W	8
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

8 May 02, 1994
D1 November 29, 1993

I, Stephan J. Szyszkoski, in a field survey on November 29, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

(D1) Quarter corner common to Section 5 T41N-R11W and Section 32 T42N-R11W. Corner reestablished in 1969 by Billy D. Buckler, RLS, midway and on line between section corners east and west. Buckler placed a 1"x36" iron pipe, buried in the E-W road and the following NBTs: 12" Hard Maple N49E 42.6', 14" Hard Maple S42W 30.5'.

(1-Sec. 5) West 1/16 corner between Section 5 T41N-R11W and Section 32 T42N-R11W. Corner established in 1982 by David B. Babbitt, RLS, midway and on a straight line between Section corner to west and Quarter corner to east. Babbitt placed a 1" I.D. pipe with a plastic RLS cap at the corner and the following witnesses: 14" Spruce S17E 27.4', 10" R. Maple N52E 49.4', 10" Hemlock N22W 48.2', 6" Spruce S29W 52.2'. Corner is buried in centerline of E-W road.

(8-Sec.5) West 1/16 corner, Section 5. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D1) Found and accepted Buckler's monument as described, at record bearing and distance from the two 1969 witnesses, both in good condition. Placed measuring nails with tags in these two trees, and marked two new NBTs as described below. Found the monument to be 0.49' North and 1.4' West of the proportionate position. Placed a location poster on a post 33.0' North of the corner.

(1-Sec. 5) Found and accepted Babbitt's monument as described, at record bearing and distance from the 1982 witnesses, all in good condition. Placed measuring nails and shiners in these trees and remeasured as shown below.

(8-Sec.5) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between quarter corner 1328.99' west and Center of Section 5 1328.99' east. The center being the unmonumented intersection of straight lines connecting opposite 1/4 corners. Monumented the 1/16 corner position with a 1" I.D. x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D1) Found 1" iron pipe buried in centerline of Leville Road.
16" Hard Maple N49E 43.15'
16" Hard Maple S42W 30.6'
Blazed, scribed, and set measuring nails in the following new bearing trees:
8" Hard Maple S05W 32.5' "1/4S NBT"
5" R. Maple N06W 39.7' "1/4S NBT"
Bearings are magnetic.

(1) Found 1" iron pipe with plastic RLS cap "Mich DNR RLS 21558"
18" Spruce S17E 28.05'
12" R. Maple N52E 49.8'
14" Hemlock N22W 48.55'
8" Spruce S29W 52.8'
Bearings are magnetic.

(8) Set 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following bearing trees:
12" Maple N73W 20.65' "W1/16 BT"
8" Maple N55W 19.1' "W1/16 BT"
12" Maple N40E 15.1' "W1/16 BT"
6" Beech S19E 29.2' "W1/16 BT"
Placed a 5" cedar post, squared and scribed, adjacent. Bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2			●	●									
3			●										
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No 33986



Date 5-11-94