

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Mackinac

(County)	Located In:	Corner Code #7
1. Public Land Survey	T 41N R 11W	C1
	T 41N R 11W	C2
	T R	
	T R	
2. Property Controlling in Section	S 5 T 41N R 11W	2
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

Register of Deeds Stamp & File Number

C2 May 02, 1994

C1 November 29, 1993

I, Stephan J. Szyszkoski in a field survey on 2 November 29, 1993 do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A Description of original monument and accessories and/or subsequent restoration.**

(C1) Corner common to Sections 5-8 T41N-R11W and Sections 31-32 T42N-R11W. Corner remonumented in 1969 by Billy D. Buckler, ALS, as follows: Corner placed in center of E-W road and midway bet. two fence corners. Found no evidence of original corner. Placed 1 1/4"x30" iron pipe in road, at corner. New bearings: 9" Cedar N20W 88.1', 8" Cedar N22E 76.0'. Found no subsequent record.

(C2) Quarter corner common to Sections 5-8. Corner reestablished in 1971 by Billy D. Buckler, ALS, midway and on a straight line between Section corners north and south. The 1971 record states: Set 1" pipe with 4" aluminum cap, 9" Soft Maple N25W 33.2', 9" Soft Maple S46W 45.0'.

(2- Sec. 5) East 1/16 corner between Section 5, T41N-R11W and Section 32, T42N-R11W. Corner established in 1982 by David B. Babbitt, ALS, midway and on a straight line between Section corner to east and quarter corner to west. Babbitt placed a 1" I.D. iron pipe with a plastic R.L.S. cap at the corner, being in the center of E-W Leville Road, and the following witnesses: 8" R. Maple S50W 45.1', 8" Beech S05W 36.3', 8" H. Maple S44E 57.3', 8" H. Maple N65E 58.1'.

**B Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

(C1) Found and accepted Buckler's monument as described at record bearing and distance from the 1969 cedar NBTs, both in good condition. Placed measuring nails with tags in the NBTs and marked two new witnesses as described below.

(C2) Found, verified the proportionate position of, and accepted Buckler's monument, found at record bearing and distance from the Maple NBT SW. The Maple NBT NW is dead and down. Set measuring nail in the 1971 NBT, marked a new top blaze, and also marked 3 new bearing trees as described below.

(2-Sec. 5) Found, verified the position of, and accepted Babbitt's monument as described, at record bearing and distance from his 1982 bearing trees. Placed measuring nails with tags in these trees, marked new top blazes, and remeasured as described below.

**C Description of monument for corner and accessories established to perpetuate locating the position of the corner**

(C1) Found 1 1/4" iron pipe buried in centerline of Leville Road.

12" Cedar N20W 86.0'

10" Cedar N22E 76.5'

Set measuring nails with tags in the following new witnesses:

Sign post "Newton Twp W16749"

South 24.3'

Telephone cable riser box N04E 34.1'

Post with location poster North 33.0'

Bearings magnetic.

(C2) Found 1" pipe with 4" MNDR cap.

Blazed, scribed, and set measuring nails in the following new bearing trees:

5" Y. Birch S68E 18.9' 1/4S NBT"

14" Maple S81W 19.8' 1/4S NBT"

5" Y. Birch N27W 6.45' 1/4S NBT"

12" Soft Maple S46W 48.3' 1/4S"

Placed a 5" cedar post, squared and

scribed, adjacent. Bearings are magnetic.

(2) Found 1" pipe with plastic RLS cap "MNDR LS 21558"

Remeasured the 1982 witnesses:

10" R. Maple S50W 45.25'

10" Beech S05W 36.7'

10" H. Maple S44E 57.8'

8" H. Maple N65E 58.45'

Bearings are magnetic.

Signed by

*Stephan J. Szyszkoski*

Date

5-11-94

Surveyor's Michigan License No

35986

