

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 41-42 NR 12 W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1, 2, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 11" Cedar (S 35 NBT) N 20 W 06 Links

6" Cedar (S 36 NBT) N 50 E 19 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by single proportionate measure along E-W township line. Many Cedar Stumps in vicinity but found no evidence of original corner. Found old blazes to south and in line with corner. Distance south 5.50 chains checks to swamp edge. Corner lies in a thick Cedar swamp. Squared and scribed 6" Cedar 6 links NE of corner.

Corner was placed and witnessed August 30, 1960.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 9/15/60