

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 41. NR. 12. W

Mackinac COUNTY

DESCRIPTION OF CORNER Meander corner for Sections 1 and 2
DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap
WITNESSES TO CORNER 9" Cedar (M.C. NBT) S 24° E 46 1/2 Links
7" Cedar (M.C. NBT) S 41° W 54 Links
8" Soft Maple (M.C. NBT) N 80° E 31 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from two Pine B.T.'s bearing N 46° W, 79 Links in excellent condition (notes indicate this bearing to be N 26° E) and N 85° E 38 Links. Low stump with B.T. Corner found by Forestry Division Survey Crew.

Corner was placed and witnessed August 29, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 9/15/60