

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ⁴11 NR 11412 W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6, 7, 1, 12
DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap
WITNESSES TO CORNER 12" Cedar (S 6 NBT) N 71° E 37 1/2 Links
6" Cedar (S 7 NBT) S 44° E 47 Links
4" Cedar (S 1 NBT) N 54° W 25 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from three Tamarack B.T. and 1 Cedar B. T. Tamarack 7" N 62° E, 15 links and Tamarack 7" N 76° W, 6 Links had Iron marks visible, Cedar 8" S 31° E, 35 Links burnt axe marks. Tamarack 8" S 27° W, 6 Links badly rotted but is proper bearing and distance.

Corner was placed and witnessed August 30, 1960.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 9/15/60