

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~41-42~~ NR 12 W

Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3, 4, 33, 34

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" White Pine (S 34 NBT) N 44° E 35 1/2 Links

6" White Pine (S 4 NBT) S 13° W 47 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by placing it on line and single proportionate measurement to section corners on town line 1 mile to east and to west. Measurement to M. C. to south and to swamp edge north check good.

Corner was placed and witnessed August 30, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/15/60
REGISTERED LAND SURVEYOR
Billy D. Buckler