

MAR 20 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey Township Corner	T41N R03W T41N R04W T42N R03W T42N R04W	A-1 ✓ M-1 A-13 M-13
2. Property Controlling in Section	S S T T R R	
3. Miscellaneous Property in Sec.	S S T T R R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

FEB 25 2000

AM PM  
7/9/10/11/12/13/14/15/16

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

*T41N R03W*  
*T42N R04W*

I, Neil E. Hill, in a field survey on 12-20-99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes William A Burt	9" Tamarack	S 67 W	36 lks
	8" Cedar	N 67 E	24 lks
1973 Glenn Bergey	6" Cedar	N 68 E	0.13 Ch
Fd rotted post and	6" Tamarack	S 38 E	0.36 Ch
2 rotted bearing stumps	7" Cedar	S 34 W	0.24 Ch
replaced with Con Mon w/	5" Spruce	N 56 W	0.21 Ch
Brass Cap			
Liber A Page 093			

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 11-12-99  
*Neil E. Hill*

No Subsequent Information

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 Fd 4" Con Mon w/ brass cap and 4 witnesses  
Accepted corner location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 4' Concrete monument with brass cap

9" Cedar	N 70 E	8.49'
9" Tamarack	S 35 E	23.57'
9" Cedar	S 35 W	15.97'
9" Spruce	N 55 W	13.85'



Bearings are compass bearings, corrected for declination, all distances are to a double-head nail in the side of the witness object unless otherwise noted.

Signature: Neil E. Hill P.S.P.C.

Date: January 21 2000

Surveyor's Michigan License No. 27447

F 00010