

**SURVEY & REMONUMENTATION**

**MAR 13 1998**

**MACKINAC COUNTY REMONUMENTATION CORNER**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>3W</u>	<u>A-12</u> ✓
Also recorded as	T <u>41N</u> R <u>4W</u>	<u>W 1/4 Sec 31</u>
	T <u>    </u> R <u>    </u>	<u>M-12</u>
	T <u>    </u> R <u>    </u>	<u>E 1/4 Cor, Sec 36</u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECEIVED & FILED  
DIANE SPAN NATION  
MACKINAC COUNTY REGISTER OF DEEDS  
DEC 29 1997  
AM PM  
71819101111213141516

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Neil E. Hill, in a field survey on DEC. 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1840 GLO notes William Burt 9" Cedar S85 1/2 W 66 lks  
5" Fir N71 1/2 W 64 lks

No records of this corner being perpetuated, however various surveys indicate this corner's position 1977 Survey by C.A.&E for Eby

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Found T-iron set by Lawrence R. Feindt with cap #21566.

- 14" Cedar S20E 37.55' (no nail)
  - 14" W. Birch S30W 30.68' (no nail)
  - 8" Spruce N55W 36.78' (no nail)
  - 12" Spruce N40W 59.20' (no nail)
- Accepted corner location.

ACCEPTED BY THE MICHIGAN SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed T-iron. Set 1/2" rod with remonumentation cap in monument box.

- Utility Pole N45W 26.13'
- 6" Cedar S35E 22.03'
- 16" Cedar S20E 38.00'
- 16" W. Birch S25W 31.29' (NE of clump of 4)



Signed by Neil E. Hill P.S.  
Surveyor's Michigan License No. 27447

Date DECEMBER 22, 1997

E-171