

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

MACKINAC COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>3W</u>	<u>WCMC B9/C9</u>
	T _____ R _____	<u>E-W Sec line</u>
	T _____ R _____	<u>Sec 19 & 30</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>#8</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECEIVED & FILED
DIANE FRANK KOVICH
MACKINAC COUNTY CLERK, OF DEEDS

DEC 29 1997
AM _____ PM _____
7|8|9|10|11|12|13|14|15|16

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Neil E. Hill, in a field survey on DECEMBER 22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1845 GLO notes William Burt 8" Tamarack S51W 1.00 ch
No records of this corner being perpetuated, however various surveys indicate this corner's location
GLO notes indicate corner set at 2242' East of 1/4 Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 No evidence of corner.
Set corner on the extension of a line from the found Section Corner and 1/4 Corner to the West.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set WCMC at 2342.00' East of 1/4 Corner and 30' from water at Lake Huron. Set 1/2" re-rod and remonumentation cap.
10" Spruce S25W 12.26'
6" W. Birch S55W 13.32'
8" Cedar S85W 12.39'
8" Cedar N50W 25.58'



Signed by Neil E. Hill P.S. Date _____
Surveyor's Michigan License No. 27447