

MAY 20 1997

1996 Mackinac County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for 'For corners in Mackinac (County)', 'Located In:', 'Corner Code #', and numbered sections 1-5 for survey details.

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTRE OF DEEDS

OCT 29 1996
AM 7|8|9|10|11|12|1|2|3|4|5|6 PM

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, David B. Guthrie, in a field survey on October 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

No record of the setting of this corner at the time of the G.L.O. Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Set 5/8" Iron Rod by single proportion between the South 1/4 Corner and Southeast Corner of Section 31, T42N-R4W.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-26-96

James H. Dranger (Signature)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set 5/8" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner placed in a Monument Box. Referenced: S08°W - 6" Cedar - 51.59 Feet, S72°W - Utility Pole - 96.66 Feet, West - 3" Alum. Remon. Cap - 6.60 Feet, N20°E - 6" W. Pine - 42.98 Feet



Signed by David B. Guthrie (Signature)

Date Oct. 10, 1996

Surveyor's Michigan License No. 22435