

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac (County) Located In: Corner Code #

- 1. Public Land Survey T 41N R 4W C-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. Recorded Plat
5. Private Claims

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS
OCT 29 1996
AM 7/8/91 PM 3/4/5/6
Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell C-1 is marked.

I, David B. Guthrie in a field survey on October 10, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced Sugar 12 - S42E - 34 / Birch 14 - S31W - 60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996: Set 5/8" Iron Rod by single proportion between the Southwest and South 1/4 Corners of Section 32, T42N-R4W.

SURVEY & REMONUMENTATION
MAY 20 1997
COMMISSION

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-26-96
James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1996: Set 5/8"x 24" Iron Rod with an Aluminum Cap stamped to identify the corner placed in a Monument Box.
Referenced: West - 3" Alum. Remon. Cap - 13.12 Feet
N62°W - Utility Pole - 95.32 Feet
S02°W - Iron Post - 33.25 Feet
S76°W - Utility Pole - 113.10 Feet



Signed by [Signature] Date Oct. 10, 1996

Surveyor's Michigan License No. 22435 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983